


PHILLIPS PETRO. CO.
R.W. Maddy No. 1

SEC. 36 T. 8 R. 18W.
C SE NE

Total Depth. 3441 P.B. 3420
Comm. 8-11-37 Comp. 9-29-37
Shot or Treated. 2000 gal.
Contractor.
Issued. 12-11-37

DEC 11 1937

County Rocks.



CASING

10" 1206' 6" 3396'

Elevation.

Production. Pot. 153 B.
2 BW.

Figures Indicate Bottom of Formations.

cellar	10
rock	20
shale and shells	490
sand and shale	630
sand streaks & shale	675
shale	845
sand	1020
shale	1048
shale and shells	1080
red bed and shells	1225
red bed and shale	1253
anhydrite	1320
shale and shells	1340
red bed and shells	1500
shaly shale and shells	1600
salt and shale	1710
lime and shale	1790
broken shale & lime	1820
shale and shells	1928
lime	1960
shale and lime	2045
lime	2090
shale and shells	2160
lime	2230
lime and shale	2340
sand	2360
lime	2403
broken lime & shale	2480
lime	2530
shale and lime	2550
lime	2580
lime and shale	2730
lime	2746
lime and shale	2785
shale and shells	2860
shale	2880
Topeka lime	3123
K.C. lime	3290
lime and shale streaks	3295
lime	3310
lime and shale	3312
lime	3325
lime and shale	3397
lime	3398
lime Arbuckle	3441
Top Arbuckle	3396
Total Depth.	

P.B. to 3420.
acid deepened hole 3' 3423.