

## WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

Company. DELTAPETRO., DEEP ROCK, CREEKMORE DRIG.  
 Farm. S. G. Schneider No. 1

SEC. 9 T. 8 R. 19W  
 NE NE SW  
 2310' N of SL, 2310' E of WL,

Total Depth. 3475

Comm. 7-26-51

Comp. 8-5-51


County Rooks

KANSAS

Shot or Treated.

Contractor. Creekmore Drilg.

Issued. 12-8-51



## CASING:

8 5/8" 260' cem w/200 sxs.

Elevation. 1917 DF

1949 (2nd)

Production. dry

Figures Indicate Bottom of Formations.

surface clay, blue shale

200

shale

280

sand, shale

1185

anhydrite

1465

shale

1775

lime, shale

3220

lime

3275

lime, shale

3423

lime

3433

lime, shale

3475

Total depth

## Tops:

Lansing

3154

Base Kansas City

3360

Arbuckle

3423

DST 1 3310-3360 Tool open

30 min. very weak blow for

3 mins. Rec. 10' slightly

oil cut mud. BHP 0# Flowing

pressure 0#; Hydro Pressure

1880#

DST 2 3412-3433 Tool open 30

min. Very weak blow for 15 mins.

Rec. 40' drilling mud. 16 min.

BHP 650#; Hydro pressure 1780#.

DST 3 3435-3475 Tool open 1 hr.

Slight blow of air during test.

Schlumberger T. D. 3475