

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

15-103-01400


Company W. L. HARTMAN
Farm Peterson No. 1

SEC. 22 T. 8 R. 19W
NW SW NW

Total Depth. 3458'
Comm. 11-21-47 Comp. 12-17-47
Shot or Treated.
Contractor.
Issued. 2-7-48

County. Rooks

KANSAS



Elevation. 2004' *2nd.*

Production. 168 BO Pot.

CASING

8 5/8" 185'
7" 3452'

Figures Indicate Bottom of Formations.

shale & shells	186
shale	320
shale & sand	1170
shale & red bed	1370
red bed & shale	1425
anhydrite	1455
shale	1640
shale, shells & salt	1865
shale & lime	2255
lime	2360
shale	2460
lime & shale	2630
shale	2680
shale & shells	2800
shale	3005
lime & shale	3085
lime	3458
Total Depth	3458'
Tops: (DF)	
Topeka	2968
Heebner	3158
Lans. K. C.	3183
Base K. C.	3407
Top Cong.	3430
Arbuckle	3449

Set 12 hours Fillup 2300' oil, 150' wtr. Rigging up will run tubing & rods. Ran bailer at 7:00 a.m. 2300' of fluid in hole. 12 hrs. ran bailer 100' off bottom full bailer of wtr. Ran bailer 150' off bottom about 1/3 of a bailer of wtr. ran bailer to bottom of hole - clean.