

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 26 T. 8 R. 19^W

API No. 15 — 163 — 20,426
County Number

Loc. SE NW NE

County Rooks

Operator Black Petroleum

Address 545 O. W. Garvey Bldg.


Well No. #1 Lease Name Veverka

Footage Location 990 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor Shields Drilling Co. Geologist Ray Dombaugh

Spud Date March 31, 1972 Total Depth 3450 P.B.T.D.

Date Completed April 9, 1972 Oil Purchaser None



Locate well correctly
Elev.: Gr. 2004

DF 2006 KB 2009

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12-1/4"	8-5/8"	28#	250	60/40 pozmix	135	3% Cal. chloride

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Thomas E. Black, d/b/a
BLACK PETROLEUM COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry hole

Well No. 1 Lease Name Veverka

S 26 T 8 R 19 E W Rooks County, Kansas


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>DRILLER'S LOG</u>				
Clay & shale		255		
Shale & shells		540		
Shale, sand & redbed		1,413		
Anhydrite		1,449		
Shale & shells		1,985		
Shale & lime		3,171		
Lime		3,450	RTD	
<u>ELECTRIC LOG TOPS</u>				
Topeka	2945	-936		
Heebner	3155	-1146		
Toronto	3178	-1169		
LKC	3195	-1186		
BKC	3415	-1406		
Arbuckle	3442	-1433		
LTD	3445	-1436		
DST #1: 3275-99/10-30-60-30, 60' MSW, BHP 1063-992#, FP 40-72#			Electra Inc.	
DST #2: 3340-80/30-30-30-30, 5' M, BHP 80-56#, FP 48-48#			Radiation Accurlog	
DST #3: 3444-70/30-30-30-30, 5' M, all press. 32#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Thomas E. Black
Signature
Owner
Title
October 24, 1973
Date

26-819W

Russell, Kansas ✓

API #15-163-20,426



SEP 8 1972


Shields

WELL LOG

Operator: Black Petroleum, Inc.
Well: Veverka #1
Commenced: March 31, 1972
Completed: April 9, 1972
Contractor: Shields Drilling Co., Inc.

Well Description:

SE NW NE
Sec. 26-8S-19W
Rooks Co., Kansas




Elevation: 2009' KB

Treatment:

Production:

D & A
ark

Tops:



CASING RECORD

Size	Run	Pulled
8 5/8"	248'	Cmtd. w/135 sax

..... Figures Indicate Bottom of Formations

Clay & shale	255'
Shale & shells	540
Shale, sand & redbed	1,413'
Anhydrite	1,449'
Shale & shells	1,985'
Shale & lime	3,171'
Lime	3,450 RTD

LOG TOPS

Topeka	2945
Heebner	3155
Toronto	3178
LKC	3195
BKC	3415
Arbuckle	3442

