

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-03178

Company - STANOLIND O & G CO.
Farm - J. A. Stice No. 2

SEC. 27 T. 8 R. 19 W
NW SE SW
990' SN1 & 1650' EWL SW $\frac{1}{4}$

Total Depth. 3405'
Comm. 11-23-46 Comp. 12-8-46
Shot or Treated.
Contractor.
Issued. 1-18-47

County. Rocks
KANSAS



CASING:

13" 151' Cem. w/200 sx.
8 5/8" 1395' Cem. w/1000 sx.
5 1/2" 3401' Cem. w/200 sx.

Elevation. 1982

Production. 2925 BOPD

Figures indicate Bottom of Formations.

surface soil	0-8
lime rock	66
sand & shells	165
shale	880
sand & redbeds	1125
shale	1385
anhydrite lime	1395
shale	2035
shale & shells	2201
lime & shale	2345
lime sdy	2655
lime	2657
shale	2801
lime & shale	3141
lime - Core #1	
3372-75 sli. inter-x	
lime por. & sli.	
oil show	3397
Core #2 - 3397-3405	
full rec., 3397-3400 1/2	
green gy shale; 3400 1/2 -	
3402 tan to buff fine	
x line tight dolomite;	
from 3402-02 1/2 buff med.	
x line dolomite. from	
3402 1/2 - 03 1/2 buff x line	
fair x line por. -	
fair show; from 3403 1/2 -	
3405 buff med. x line	
vugular and inter-x	
line, very good oil	
show. Hole filled	
300' w/oil after drlg.	
plug - acidized w/1000	
gals. dowell F22;	
Private test by Deptho.	
I.C. 2466'	
Arbuckle Lime	3405
Total Depth.	

3135
1385
-1750

Sand & red beds 880-1125'

Tops:

Lansing Lime 3135
Arbuckle Lime 3400 1/2 - 3405

Potential 2925 BOPD by 3-point
Drawdown pumped through tbgs.