

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

15-163-70870


Company - STANOLIND OIL & GAS CO.  
Farm - J. A. Stice No. 3

SEC. 27 T. 8 R. 19W  
CS  $\frac{1}{2}$  NE SW  
1650'N SL & 1980'E WL SW  $\frac{1}{2}$

Total Depth. 3405'  
Comm. 2-26-47 Comp. 3-17-47  
Shot or Treated. Acid.  
Contractor.  
Issued. 4-19-47

County. Rooks

KANSAS



Elevation. 1977

Production. D.D., Pot. 3728 BO No Wtr

Figures Indicate Bottom of Formations Drawdown

sand & shale	0-170	Acidized With 500 gal.	
shale blue	315	Dowell F22. State Pot.	
sand & shells	410	3 point Depthograph	
shale	585	Drawdown 1.C. 3728 Oil,	
sand & pyrite	600	no wtr. Pumped through 2 $\frac{1}{2}$ " Tubing,	
sand & shale	685	7/8" rods & 2 $\frac{1}{2}$ " x 2" insert pump.	
sand	745		
shale, sand & clay	765	ARBUCKLE LIME	3505
sdv shale	771		
sand & shale	831	Tops:	
shale	885	Lansing Lime	3127
sand	990	Arbuckle Lime	3401-3405
sand & shale	1105		
sand	1120		
shale & red rock	1155		
red bed, shale & sand	1240		
red bed & shells	1380		
anhydrite	1425		
red bed & shale	1650		
shale & shells	1710		
shale & salt	1800		
shale & shells	1860		
lime & shale	1880		
lime	1925		
lime & shale	1940		
sdv lime & shale strks	2000		
lime & shale	2120		
lime	2130		
lime & shale	2244		
lime, shale & iron	2272		
lime & shale	2415		
sand lime & shale	2465		
sdv lime	2610		
sdv lime & shale	2680		
shale & lime	3000		
lime & shale	3055		
lime	3175		
lime hd	3245		
lime & shale	3280		
lime	3388		
Core #1 Rec. 2/2			
Gry. Fn. Xln. Dense Fossil,			
Glaucontic - Ls.	3390		

3127  
1380  
1747

Core #2 Rec. 9/10  
4' Greenish Grysh, 3' Tan  
Shaley Fossil Tight-Ls.  
2' Tan Tight Pyritic Dolo.  
Inclusions - Ls. 3400

Core #3 Rec. 3/5  
1' Tan Micro Xln. Shaley  
Sdy Tight Dolo. 1  $\frac{1}{2}$ ' Tan &  
Pink Micro to Fn, Xln. Sdy  
Large Vugs Dolo. Bleeding Oil,  
 $\frac{1}{2}$ ' Tan Micro Xln. Small Vugs. S  
Shaley Tight Dolo. 3405  
Total Depth