

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas


15-163-03179

Company W. H. BIRD ET AL
Farm Veverka No. 8

SEC. 28 T. 8 R. 19W
SE NE NE

Total Depth. 3458'
Comm. 10-3-47 Comp. 10-22-47
Shot or Treated.
Contractor. Glenn W. Peel
Logging 1-31-48

County. Rooks
KANSAS



CASING:

8-5/8" OD 260' Cem. w/125 sx
5-1/2" 3452' Cem. w/100 sx

Elevation. 2011.2nd.

Production. 83 BO & 50 BW

Figures indicate Bottom of Formations.

sand	0-65
shale	143
shale & shells	591
sand	621
shale & shells	748
sand	782
shale & shells	930
sand	1176
shale & shells	1443
anhydrite	1479
shale & shells	1620
lime & shale	1787
anhydrite & shale	1853
lime bro. and shale	1950
lime & shale	2467
lime	2572
lime & shale	2990
lime	3012
lime & shale	3087
lime	3172
lime & shale	3223
lime RTD	3453
3453= 3451 D.F.	
Cable Tools:	
lime	3458
Total Depth	

Tops: (DF)
Lansing 3175
Base K. C. 3423
Arbuckle 3448