

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H. BIRD & GLENN W. PEEL
Farm - Veverka No. 9

15-163-03182
SEC. 28 T. 8 R. 19W
NW NE SE

Total Depth. 3485'

Comm. 12-6-48

Comp. 12-18-48


Shot or Treated.

Contractor. Plenn Peel Drlg. Co., Inc.

Issued. 4-9-49

County. Rooks

KANSAS



CASING:

8-5/8" 280' Cemented

5-1/2" 3480' Cemented

Elevation. _____

Production. 44 BO & 93% wtr.

Figures Indicate Bottom of Formations.

surface clay	60
sand	74
shale	260
sand	270
shale	280
shale & shells	540
sand & shale	620
shale	823
lime	828
shale & shells	950
sand & shale	1150
shale & red bed	1335
shale	1480
lime	1505
shale & shells	1635
shale & lime	1920
lime & shale	2470
lime	2730
lime & shale	3085
lime RTD	3485
Total Depth	

Tops; D.F.

Lansing 3174

no commercial shows in

Lansing K. C.

Base K. C. 3114

Arbuckle 3440

Good show oil 3440-44' D.F.

spotted staining 3446-56 D.F.

Very good show oil 3455-57 D.F.

lgt odor & stain 3459-63 D.F.

Spotted sat. & lgt odor 3480-82 D.F.