

30-8-19W
15-168-20,585

OPERATOR:
CONTRACTOR:
W NAME:
LOCATION:

Kansas Petroleum, Inc.
Abercrombie Drilling, Inc.
WOLFENDER #1
C SW NE SE Sec. 30-8S-19W
Rooks County, Kansas

GEOLOGIST:
SPUD DATE:
COMPLETION DATE:

Dick Roby
October 20, 1975
October 28, 1975

0	100	Post rock
100	180	Clay and Sand
180	220	Shale
220	881	Shale and Sand
881	1464	Shale
1464	1498	Anhydrite
1498	2663	Shale
2663	2961	Shale and Lime
2961	3265	Lime and Shale
3265	3450	Lime
	3450	Rotary Total Depth

Cut 220' of 12 1/4" hole. Ran 5 joints 8 5/8" casing. Set @ 216.42. Cemented with 165 . HA 5.. Cemented circulated. Plug was down at 8:30 p.m. October 20, 1975.

Ran 5 1/2" casing. Plug was down 1:30 a.m. October 28, 1975.

SAMPLE TOPS:

Anhydrite 1464'
B/Anhydrite 1498'

