

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock

Wichita, Kansas


15-103-03184

Company - HEATHMAN-HONAKER DRLG. CO., INC.
Farm - T. Ondrasek No. 1

SEC. 31 T. 8 R. 19W
SE SE NE

K.B.
Total Depth. 3502' PB 3497
Comm. 4-9-49 Comp. 4-19-49
Shot or Treated. Acid
Contractor. Heathman-Honaker Drlg
Issued. 8-27-49

County. Rooks KANSAS



Elevation. 2049 (br)
2051 (end)

Production. ~~32 bbl oil & no wtr.~~
1217 wbs per day

CASING:

8 5/8 173.09 w/125 sx. cem. & 1 sx C.C.
5 1/2 3496' w/125 sx. cem. 2' off bottom

Figures Indicate Bottom of Formations.

sand & shale 189
shale, shells & sand 1300
shale, shells 1512
anhyd. 1548
shale & shells 1945
shale, shells 2233
shale & lime 3290
limo 3435
lime & shale RTD 3498
lime & shale 3502
Total Depth K.B. P. B. 3497
Tops:
Anhyd. 1512
Topeka 3004
Heebner 3208
Lansing -K. C. 3249
Arbuckle 3495
R.T.D.

Cable Tool:

Cleaned out to 3498 T. D. - no shows
Drilled deeper 3498 to 3499-7 gal. oil 3 hrs.
Drilled deeper 3499 to 3500, filled 60' oil 7 hrs.
To acidize w/500 gal. (as of 4-25-49)
Drilled to 3502 T.D. (KB), made 1/2 BOPH;
caving, to run plastic.
4-28-49 Plugged back from 3502 to 3497
(KB) w/sand; used 50 gal. plastic @ 1800#
pressure.
4-29-to 5-1-49 - Gave 24 shots (Lane-Wells
guns) from 3497 1/2 to 3501 1/2. Acidized w/
1000 gals. Dowell; pressure went down to
1000#; gave another 1000 gal. acid; swabbed
to bottom; filled up 1000' in 1 hr.; let
set 8 hrs; filled up 2733', no wtr. Statted
swabbing 1700' off bottom. Swabbed 32
BOPH, no wtr. 1st hour; swabbed 22 BOPH
no wtr 2nd hr.. Ran Gamma Ray. To run
tubing & rods & put on pump.