

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
 508 EAST MURDOCK - WICHITA, KANSAS

15-163-70098

COMPANY DEEP ROCK OIL CORPORATION

SEC. 32 T. 8 R. 19W

FARM John Ondrasek no. 8

LOC. NW SE NW
 990' W. EL, 990' N. SL/ NW/4

TOTAL DEPTH 3491; PB to 3422

COUNTY Rocks


COMM. 12-6-50

COMP. 12-30-50

SHOT OR TREATED

CONTRACTOR Heathman Drlg. Co; Drlg. In; O. H. Tice Drlg. Co.

ISSUED 2-17-51



CASING

10 3/4" 125' cem. w/100 sx
 7" 3489' cem. w/250 sx

2042

ELEVATION 2040' D. F.

PRODUCTION IPP 180 bbls. oil & no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & sand	610	3385-3405 - #4 - Open one
shale	1020	hour, strong blow throughout;
sand	1170	recovered 1260' of live gassy
sand & shale	1509	oil & 60' of oily mud, or
Anhydrite	1548	muddy oil. BHP 870 psi.
shale & shells	1605	Flowing pressure 260 psi.
shale	1850	Record of Coring:
shale & shells	1950	Cored 3489-3491, recovered 2'
shale & lime shells	2105	Arbuckle dolomite. Top 1'
shale & lime	2720	dolomite with cracks and vugs
shale	2969	plugged with green clay. Bled
lime & shale	3245	oil. Bottom 1' consisted of
lime	3462	green clay w/chert nodules and
lime & shale	3489	rare dolomite nubbins and is
lime (cored)	3491	definitely not reservoir
Total depth		material.
Tops:		Perf. 3390-3402 w/60. Swb. &
Anhydrite	1509	bailed about 10 gals. of oil
Topeka	2994	per hr.
Heebner	3202	12-29-50; Acidized w/500 gals.
Lansing Kansas City	3241	Loaded hole w/wtr, 138 bbls.
Base Kansas City	3459	Top treating pressure 300#. Pressure
Arbuckle	3488	to zero in 5 mins. Swb. well.
Elevations	2037 Gr.	Made 109.5 bbls. oil in 8 1/2 hrs.
	2042 R.B.	Well placed on pump.

All Perforations in Fifth Zone

12-28-50 12/3391-3395
 12/3395-3399
 12/3398-3402
 12/3398-3394
 12/3394-3390

3240
 1510
 1730

12-29-50 3390-3402', 500 gals. acid.

Lansing-Kansas City 3241-3459'
 12-29-50, Swabbed 110 bbls. oil in 8 1/2 hrs, thru csg.

Record of Drill Stem Tests

3258-3285 #1 - open 45 minutes, weak blow for 18 minutes; recovered two feet of free oil & 18' of rotary mud. BHP zero. 3300-3318 - #2 -open 50 minutes; recovered two feet of free oil & 13' of oil cut mud. BHP zero. 3356-3385 - #3 -Open one hr; recovered 75' of oil & gas cut mud. BHP zero.