

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

505 E. Murdock, Wichita, Kansas

15-163-02439

Company - CITIES SERVICE OIL CO.  
Farm - Swalp No. 1

SEC. 32 T. 8 R. 19W  
NW NW SW 330' S & 330' E.  
of 1/4 corner

Total Depth. 3592  
Comm. 8-28-49 Comp. 9-9-49  
Shot or Treated.  
Contractor. Transit Corp.  
Issued. 10-15-49

County. Rooks

KANSAS



Elevation. 2057 *ft*

Production. Dry

CASING:  
8 5/8" 1529' cem. w/650 sx.

Figures Indicate Bottom of Formations.

surface soil & shale	65
shale	395
shale & shells	565
sand & shells	750
shale & shells	990
sand & shale	1190
shale & red bed	1325
red bed	1465
red bed & shells	1519
anhyd.	1553
red bed, shells & shale	1860
shale & shells	2035
shale, salt & shells	2080
shale, sand & lime	2230
lime & shale	2835
lime sdy	2930
shale sdy	3000
lime brkn	3060
lime & shale	3235
lime	3505
shale, red & chert	3535
lime, shale & chert	3550
shale, lime & chert	3572
lime & chert	3592
Total Depth	

Tops:	
Topoka	3016
Heebner	3223
Dodge	3249
Lansing	3266
Congl.	3503
Simpson shale	3539
Arbuckle	3560

Pen. 32'

D.S.T. 3562-72 rec. 95' muddy wtr in 30 mins.

Ran Schlumberger electric log.  
P. A. 9-10-49