

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-70 226

Company AMERADA PETROLEUM CORPORATION
Farm Lowry No. 1

SEC. 33 T. 8 R. 19 W

CN/2 NE NE

Total Depth. 3487

Comm. 9-10-46

Comp. 9-20-46


Shot or Treated.

Contractor. Glenn W. Peel

Issued. 11-2-46

County. Rooks

KANSAS



Elevation. 1988

CASING:
8-5/8" 1420 Cem.

Production. Dry Hole

Figures Indicate Bottom of Formations.

surface soil	10
post rock	60
sand & shale	270
shale & shells	530
sand	685
shale & shells	850
sand	870
shale	900
sand	975
sand	1100
sand & shells	1145
shale	1405
anhydrite	1415
"	1421
"	1445
shale & shells	1605
shale & sand	1985
shale & shells	2163
shale	2165
shale & shells	2465
lime	2475
shale & shells	2625
lime	2680
shale	2818
lime & shale	2996
shale	3121
lime	3439
Arbuckle dolomite	3487
Total depth	

DEEPENING RECORD

Comm: 10-22-47

Comp: 11-26-47

W.H. Bird Etal

Production: S.W. D.W.

5 1/2" casing 3535' D.F. cem w/200 sx.

tight xlyn dolo. Spotted porosity,
few shale stringers 3484-3550

xlyn dolo, good porosity 3475

tight xlyn dolo. 3485

xlyn porous dolo. 3610

tight xly dolo. strks of

shale, spotted 3660

Porosity

xlyn dolo, med porosity

3730

tight xlyn dolo. 3750

about same plus some spotted

good porosity 3750

med tight xlyn dalomite

3800

Total depth

Tops:

Arbuckle 3437 D.F.

Soft porous zones, 3535-68 and 3584-98 and
3601-10 and 3618-34, 3649-57, 3662-3706
and 3742-48.

Tops:

Anhydrite	1402
Base K.C.	3364
Arbuckle	3436

SLOAN, CHAIRMAN
ERNEST E. PLINQUE
HOMER HOCH
COMMISSIONERS

LEO B. WHITE, SECRETARY
ERIC D. HARRIS, ATTORNEY

FILED 20492 12 11 33

WICHITA BRANCH

State Geological Survey P1

State Geological Survey
WICHITA BRANCH

W. H. BIRD et al
TOKALSA, OK

#1 Lowery
STATE OF KANSAS

ON/2 NE/4 NE/4 33-8-19W
Rooks County, Kansas

Salt Water Disposal CORPORATION

CONSOLIDATION DIVISION

LOS ANGELES, CALIF.

WICHITA, KANSAS

Elevation 1988'

15-163-70226
Hardman

November 31, 1947

- 3484-3550 Tight crystalline dolomite - spotted porosity -
few shale stringers
3475 Crystalline dolomite - good porosity
3485 Tight Crystalline dolomite
3610 Crystalline porous dolomite
3660 Tight crystalline dolomite - streaks of shale -
spotted porosity
3730 Crystalline dolomite - medium porosity
3750 Tight crystalline dolomite
3750 About same plus some spotted good porosity
3800 Medium tight crystalline dolomite

This assessment, payable within thirty (30) days
from submission of this statement, for books of
administration located under the provisions of
Sections 35-301 and 344 General Statutes of Kansas,
1935, relating to active book No. 3437, has been
determined as explained and ordered in vol. 1005 of
the Commission's Order No. 28-07-35.

GEOLOGICAL DATA

IN ACCOUNT WITH - CONSOLIDATION DIVISION
Top Arbuckle STATE CORPORATION 3437 D.F.
800 Billings Bldg.
Wichita, Kansas. 3800 D.F.

PI 5 1/2" Cemented @ 3535 D.F. (200 sax)

- Soft porous zones 3535-68 & 3584-98 & 3601-10 &
3618-34 & 3649-57 & 3662-3706
& 3742-48

LEGAL DESC. LEASE 33-8-19W

COUNTY

Rooks

Assessment for one Lease 113.00
Assessment for additional Lease 400.00
Total Assessment per above Order 513.00

Payment made 11/25, 1947