

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - SKELLY OIL COMPANY  
Farm - Frank Rostocil No. 2

SEC. 33 T. 8 R. 19W

330' fr. S.  
330' fr S1S1/4

County. Rooks

KANSAS



Total Depth. 3531'  
Comm. 7-23-48 Comp. 6-7-48  
Shot or Treated.  
Contractor. Wentworth Drilling Co., Inc.  
Issued. 9-1-48

CASING:

8 5/8" 1440' Cem w/600 Sx.

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	40
sand and shells	165
shale	860
sand and shale	1145
shale	1230
shale & red bed	1430
anhydrite	1440
anhydrite	1470
shale and shells	1555
shale and shells	2235
lime and shale	2800
lime, broken	2885
lime and shale	3165
lime	3457
dolomite, grey and brown	3461
weathered dolomite, sand	
shale & chert conglomerate	3514
dolomite, hard buff dense	3531
total depth	

Tops:

Heebner Shale	3168'
Lansing Lime	3209
Slight porosity and oil stain	
Ran Halliburton drill stem test	
with packer set at 3442', open	
30 minutes, recovered 10' med.	
Arbuckle Lime	3514
No shows	
Conglomerate	3457

3209  
1430  
1779

Slight porosity and  
oil stain 3457-3461'

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL COMPANY  
Farm - Frank Rostocil No. 2


SEC. 33 T. 8 R. 19W

SESESW  
330' fm S1SW/4  
330' fm S1SW/4

DEEPENING RECORD

Total Depth. 3889  
Comm. 7-23-48 Comp. 6-7-48 ✓  
Shot or Treated.  
Contractor. Wentworth Drilling Co., Inc.  
Issued. 5-13-50

County. Rocks  
KANSAS



CASING:

8 5/8" 1440' Cem w/600 Sx.

Elevation. 2014' and!

Production. S.L.D.W.

Figures Indicate Bottom of Formations.

surface soil	40
sand and shells	165
shale	860
sand and shale	1145
shale	1230
shale & red bed	1430
anhydrite	1440
anhydrite	1470
shale and shells	1555
shale and shells	2235
lime and shale	2800
lime, broken	2885
lime and shale	3165
lime	3457
dolomite, grey and brown	3461
weathered dolomite, sand	
shale & chert conglomerate	3514
dolomite, hard buff dense	3531
total depth	
Tops:	
Heebner Shale	3168'
Lansing Lime	3209
Slight porosity and oil stain	
Ran Halliburton drill stem test	
with packer set at 3442', open	
30 minutes, recovered 10' med.	
Arbuckle Lime	3514
No shows	
Conglomerate	3457
Slight porosity and	
oil stain	3457-3461'

DEEPENING RECORD

Skelly Oil Co.  
Comm: 1-21-50  
Comp: 2-26-50  
Contractor C. Wentworth Drlg. Co.  
Production: S.L.D.W.  
5" 3743' SLM cem w/350 sx.  
lime 3862 1/2  
quartzite 3895  
SLM Corr: 3895 rotary table  
equals 3869' SLM derrick floor.  
Total depth

Tops:  
Arbuckle lime 3514  
Quartzite 3862 1/2

Spot or acid treatment:  
2-2-50, 2000 gals from 3745-3869'  
2-4-50, 6000 gals from 3518-3821'.  
Input formation: Arbuckle(Basal) 3518-  
3889'.