


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company SKELIY OIL CO.  
Farm Mable McCauloy No. 1.

SEC. 34 T. 8 R. 19 W  
SE SW SE  
330' fsl 990' fwl SE  $\frac{1}{4}$

Total Depth. 3535  
Comm. 4-22-46 Comp. 5-9-46  
Shot or Treated.  
Contractor. Claude Montworth Drlg. Co.  
Issued. 7-13-46 Rotary O-3535

County. Rooks  
KANSAS



Elevation. 2000

Production. Dry

CASING:  
13 3/8" 159' Com.  
8 5/8" 1445' Com.  
5 1/2" 3521' Com.

Figures Indicate Bottom of Formations.

surface soil	68
sand & gravel	130
lime & shale	162
shale & shells	435
shale, shells & clay	550
gravel & shells	520
shale & shells	905
sand	1050
shale, shells & red rock	1180
red bed & shells	1240
sand & pyrite	1285
shale, shells & red rock	1320
red bed & shells	1440
anhydrite	1475
red bed & shale	1850
salt	1900
shale & lime	2230
lime sdy	2260
lime	2285
lime & shale	2670
shale	2720
shale & lime	2825
lime	2875
shale & lime	2895
shale	2965
lime & shale	3155
lime	3226
lime & chert	3231
lime & shale	3382
oolitic & xlyn lime, mod. porosity & oil saturation, probable water	3530
lime & shale	3424
lime, shale & red rock	3500
chert	3507
lime, shale & chert	3520
gy xlyn dolomite	3535
Total Depth	

3211  
1440  

---

1771

Tops:  
Ft. Dodge Lime 3190  
Lansing Lime 3211  
Simpson Shale 3511  
Arbuckle Lime 3520

3382-3390 Med. por. & sat.,  
probable water

5-14-46 shot 750 qts. 3380-3401  
5-16-46 shot 2500 qts. 3380-3401