

15-163-2054e

24-8-19W

State Geological Survey  
WICHITA, BRANCH

DRILLERS' WELL LOG

DATE COMMENCED: November 20, 1974  
DATE COMPLETED: November 29, 1974

PETROLEUM, INC.  
VEVERKA "G" #1  
NW NW NE  
Sec 34-T8S-R19W  
Rooks County, Kansas

ELEVATION: 1957 K.B.

- 0 - 35' Shale
- 35 - 45' Post Rock & Hard Sand
- 45 - 206' Blue Shale & Sand Streaks
- 206 - 505' Shale
- 505 - 536' Sand
- 536 - 820' Shale & Sand Streaks
- 820 - 1095' Red Bed & Sand
- 1095 - 1255' Shale & Shells
- 1255 - 1366' Shale
- 1366 - 1405' Anhydrite
- 1405 - 1830' Shale & Shells
- 1830 - 3102' Lime & Shale
- 3102 - 3106' Shale
- 3106 - 3144' Lime & Shale
- 3144 - 3387' Lime
- 3387 - 3415' Dolomite

FORMATION DATA

Anhydrite	1366
Heebner	3102
Toronto	3128
Lansing	3144
Arbuckle	3387
RTD	3415

RECEIVED  
STATE CORPORATION COMMISSION

DEC 4 1974

CONSERVATION DIVISION  
Wichita, Kansas

SURFACE PIPE: Set 206'  
of 8-5/8", 20# pipe with  
130 sacks common cement,  
2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON ) SS

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.



Wayne Dobbs

Subscribed and sworn to before me this 3rd day of December 1974.

My Comm. Expires:  
April 11, 1978

Douglas M. Hague  
Notary Public