

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-163-03188

Company- STRAIN DRILLING et al
Farm- Slansky "A" No. 1

SEC. 35 T. 8 R. 19W
OS/2 SE SW

Total Depth. 3409 RB
Comm. 3-2-51 Comp. 3-12-51
Shot or Treated.
Contractor.
Issued. 12-1-51

County
Rocks
KANSAS



8 5/8" CASING:
130' cem w/75 sx.
4 1/2" 3404' cem w/125 sx.

1961 (m)
Elevation. 1963 DE
1966 (end)
Production. 104 bbls

Figures Indicate Bottom of Formations.

sand, shale	30
shale	128
shale, shells	730
shale	840
sand	1090
red rock, shale	1365
anhydrite	1405
shale, shells	1930
lime, shells	1975
lime	2090
lime, shells	2200
lime	2425
lime, shale	2630
shale	2785
shale, lime	3005
shale	3034
lime	3050
shells, lime	3105
lime	3405
ar buckle	3409 RB
Total Depth	

Tops:
Anhydrite 1365
Heebner 3111
Kansas ity 3151
Ar buckle 3402

DST:
3302-28 open 15 min.
Rec. 410' mud cut salt
water BHP 1100 - 15 min.

3404-09 open 30 min.
Rec. 260' green oil, 60' oil
gas cut mud BHP 950# - 15 min.