

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock, Wichita, Kansas


15-163-00329

Company - DEEP ROCK & CREEKMORE DRIG. & DELTA PETRO. SEC. 20 T. 8 R. 20W
 Farm - Normandin No. 1 NW NW NW

330' S of NL, 330 E of WL
 of NW/4

County. Rooks

KANSAS



Total Depth. 3700

Comm. 6-11-51

Comp. 6-22-51

Shot or Treated.

Contractor. Creekmore Drig. Co.

Issued. 7-21-51

CASING:

8 5/8" 216 cem w/175 sxs.

Elevation. 2065 DF

2063(m)

Production. dry

Figures Indicate Bottom of Formations.

sand, clay	45
sand, shale	1360
shale, broken lime	1660
anhydrite	2000
shale, lime	2370
broken lime	2430
lime, shale	2560
broken lime, shale	2795
shale	2915
shale, broken lime	3045
shale, lime	3350
lime	3462
lime, shale	3510
lime	3440
lime, shale	3690
lime	3700
Total depth	

Tops:

Topeka	3066
Heebner	3278
Toronto	3302
Lansing	3319
Conglomerate	3610
Arbuckle	3648

DST #1 3460-3540 tool open 30 min., weak blow for 12 minutes. rec. 15' very slightly oil cut mud. BHP #0

DST #2 3652-3700 tool open 1 hr. good continuous blow, rec. 285' salt wtr. show of free oil on tester valve. BHP 900# Flowing pressure 135#

Record of Plugging:

Drillers T. D. 3700

Schlumberger T. D. 3701

Plugging commenced 6-22-51

Filled hole with heavy mud from 3700-240'. Set plug at 240.

Pmped in 95 sxs of cement through drill pipe by Halliburton. to top of cell.