


KCC
APR 24 2006
CONFIDENTIAL



DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc**

PO Box 399
Garden City KS 67846

ATTN: Steve Murphy

7-8s-21w-Graham

Riggs #1-7

Start Date: 2006.02.19 @ 01:35:36

End Date: 2006.02.19 @ 12:40:36

Job Ticket #: 24646 DST #: 1

RECEIVED
APR 26 2006
KCC WICHITA

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

American Warrior Inc


Riggs #1-7

7-8s-21w-Graham

DST # 1

LKC-"C-F"

2006.02.19



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc

PO Box 399
Garden City KS 67846

ATTN: Steve Murphy

Riggs #1-7

7-8s-21w-Graham

Job Ticket: 24646

DST#: 1

Test Start: 2006.02.19 @ 01:35:36

GENERAL INFORMATION:

Formation: **LKC-"C-F"**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 05:03:21

Time Test Ended: 12:40:36

Test Type: **Conventional Bottom Hole**

Tester: **Jason McLemore**

Unit No: **32**

Interval: **3257.00 ft (KB) To 3325.00 ft (KB) (TVD)**

Total Depth: **3325.00 ft (KB) (TVD)**

Hole Diameter: **7.80 inches** Hole Condition: **Good**

Reference Elevations: **2033.00 ft (KB)**

2028.00 ft (CF)

KB to GR/CF: **5.00 ft**

Serial #: 6719

Inside

Press@RunDepth: **433.77 psig @ 3260.00 ft (KB)**

Start Date: **2006.02.19**

End Date:

2006.02.19

Capacity: **7000.00 psig**

Last Calib.: **2006.02.19**

Start Time: **01:35:38**

End Time:

12:40:36

Time On Btm: **2006.02.19 @ 05:02:51**


Time Off Btm: **2006.02.19 @ 07:33:21**

TEST COMMENT: IFP-Fair Blow ,Built to 8-1/2"

ISI-Dead

FFP-Weak Blow ,Built to 2"

FSI-Dead



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1584.46	102.86	Initial Hydro-static
1	50.67	102.62	Open To Flow (1)
33	283.69	109.04	Shut-In(1)
61	870.38	109.20	End Shut-In(1)
62	291.65	108.93	Open To Flow (2)
91	433.77	109.53	Shut-In(2)
150	866.61	109.46	End Shut-In(2)
151	1572.85	109.42	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
248.00	MMV-90%W-10%M	3.20
186.00	HOCMMV-15%G-35%O-40%W-10%M	2.61
248.00	HOCMMV-15%G-45%O-25%W-15%M	3.48
186.00	HOCMMV-15%G-55%O-10%W-20%M	2.61
186.00	CGO-20%G-80%O	2.61

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc

Riggs #1-7

PO Box 399
Garden City KS 67846

7-8s-21w-Graham

Job Ticket: 24646

DST#: 1 APR 24 2006

ATTN: Steve Murphy


Test Start: 2006.02.19 @ 01:35:36

KCC
CONFIDENTIAL

Tool Information

Drill Pipe:	Length: 3215.00 ft	Diameter: 3.80 inches	Volume: 45.10 bbl	Tool Weight: 2200.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 2.70 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 31.00 ft	Diameter: 2.25 inches	Volume: 0.15 bbl	Weight to Pull Loose: lb
		Total Volume: 45.25 bbl		Tool Chased 0.00 ft
Drill Pipe Above KB:	17.00 ft			String Weight: Initial lb
Depth to Top Packer:	3257.00 ft			Final lb
Depth to Bottom Packer:	ft			
Interval between Packers:	68.00 ft			
Tool Length:	96.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3230.00	
Shut In Tool	5.00			3235.00	
Hydraulic tool	5.00			3240.00	
Jars	5.00			3245.00	
Safety Joint	2.00			3247.00	
Packer	5.00			3252.00	28.00 Bottom Of Top Packer
Packer	5.00			3257.00	
Stubb	1.00			3258.00	
Perforations	1.00			3259.00	
Change Over Sub	1.00			3260.00	
Recorder	0.00	6719	Inside	3260.00	
Blank Spacing	31.00			3291.00	
Change Over Sub	1.00			3292.00	
Perforations	30.00			3322.00	
Recorder	0.00	13221	Outside	3322.00	
Bullnose	3.00			3325.00	68.00 Bottom Packers & Anchor
Total Tool Length:	96.00				



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc

Riggs #1-7

PO Box 399
Garden City KS 67846

7-8s-21w-Graham

Job Ticket: 24646

DST#: 1

ATTN: Steve Murphy

Test Start: 2006.02.19 @ 01:35:36

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

36 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

18000 ppm

Viscosity: 46.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.99 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 1500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
248.00	MM-90%W-10%M	3.196
186.00	HOCMM-15%G-35%O-40%W-10%M	2.609
248.00	HOCMM-15%G-45%O-25%W-15%M	3.479
186.00	HOCMM-15%G-55%O-10%W-20%M	2.609
186.00	CGO-20%G-80%O	2.609

Total Length: 1054.00 ft

Total Volume: 14.502 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: 300' GIP

DST Test Number: 1


7-8s-21w -Graham

American Warrior Inc

Inside

Serial #: 6719

Pressure vs. Time



Trilobite Testing, Inc

Ref. No: 24646

Printed: 2006.03.01 @ 09:43:48 Page 16