


15-065-23249



**TRILOBITE
TESTING, INC.**

KCC
DEC 21 2006
CONFIDENTIAL

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc**

P O Box 399
Garden City KS 67846

ATTN: Cecil O'Brate

6 8 21 Graham KS

Gosselin # 2-6

Start Date: 2006.11.14 @ 20:47:54

End Date: 2006.11.15 @ 06:02:54

Job Ticket #: 25220 DST #: 1

Trilobite Testing, Inc
PO Box 362 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 22 2006

CONSERVATION DIVISION
WICHITA, KS

Printed: 2006.11.15 @ 11:26:49 Page 1

American Warrior Inc

Gosselin # 2-6

6 8 21 Graham KS

DST # 1

C-D

LKC

2006.11.14



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc
P O Box 399
Garden City KS 67846
ATTN: Cecil O'Brate

Gosselin # 2-6

6 8 21 Graham KS

Job Ticket: 25220

DST#: 1

Test Start: 2006.11.14 @ 20:47:54

GENERAL INFORMATION:

Formation: C-D LKC

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 23:50:09

Time Test Ended: 06:02:54

Test Type: Conventional Bottom Hole

Tester: Dan Bangle

Unit No: 38

Interval: 3345.00 ft (KB) To 3391.00 ft (KB) (TVD)

Total Depth: 3391.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Reference Elevations: ft (KB)

ft (CF)

KB to GRV/CF: ft

Serial #: 6741

Inside

Press@RunDepth: 240.18 psig @ 3348.00 ft (KB)

Start Date: 2006.11.14

End Date:

2006.11.15

Start Time: 20:47:56

End Time:

06:02:54


Capacity: 7000.00 psig

Last Calib.: 2006.11.15

Time On Btm: 2006.11.14 @ 23:49:54

Time Off Btm: 2006.11.15 @ 02:54:24

TEST COMMENT: IF Strong B-B in 10 min
ISI Weak 1/2 " steady blow
FF Weak building to 3 "
FSI Weak steady surface blow



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1630.41	99.92	Initial Hydro-static
1	27.78	99.63	Open To Flow (1)
46	157.91	104.25	Shut-In(1)
91	672.42	105.72	End Shut-In(1)
91	164.32	105.56	Open To Flow (2)
134	240.18	106.62	Shut-In(2)
185	626.09	106.92	End Shut-In(2)
185	1564.43	107.48	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
60.00	OCM 40%O 60%M	0.84
620.00	CGsyO 10%G 90%O	8.70
0.00	330 GIP	0.00

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc

Gosselin # 2-6

P O Box 399
Garden City KS 67846

6 8 21 Graham KS

Job Ticket: 25220

DST#: 1

ATTN: Cecil O'Brate

Test Start: 2006.11.14 @ 20:47:54

Tool Information

Drill Pipe:	Length: 3343.00 ft	Diameter: 3.80 inches	Volume: 46.89 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	20000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose:	45000.00 lb
			Total Volume: 46.89 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	19.00 ft			String Weight: Initial	32000.00 lb
Depth to Top Packer:	3345.00 ft			Final	35000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	51.00 ft				
Tool Length:	72.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
------------------	-------------	------------	----------	------------	----------------

Change Over Sub	1.00			3325.00	
Shut In Tool	5.00			3330.00	
Hydraulic tool	5.00			3335.00	
Packer	5.00			3340.00	21.00 Bottom Of Top Packer
Packer	5.00			3345.00	
Stubb	1.00			3346.00	
Perforations	1.00			3347.00	
Change Over Sub	1.00			3348.00	
Recorder	0.00	6741	Inside	3348.00	
Drill Pipe	31.00			3379.00	
Change Over Sub	1.00			3380.00	
Recorder	0.00	13254	Outside	3380.00	
Perforations	8.00			3388.00	
Bullnose	8.00			3396.00	51.00 Bottom Packers & Anchor

Total Tool Length: 72.00

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 22 2006
CONSERVATION DIVISION
WICHITA, KS



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc

Gosselin # 2-6

P O Box 399
Garden City KS 67846

6 8 21 Graham KS

Job Ticket: 25220

DST#: 1

ATTN: Cecil O'Brate

Test Start: 2006.11.14 @ 20:47:54

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 56.00 sec/qt

Cushion Volume:

bbl

Water Loss: 6.80 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 1200.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
60.00	OCM 40%O 60%M	0.842
620.00	CGsyO 10%G 90%O	8.697
0.00	330 GIP	0.000

Total Length: 680.00 ft

Total Volume: 9.539 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

DST Test Number: 1


6 8 21 Graham KS

American Warrior Inc

Inside

Serial #: 6741

Pressure vs. Time



RECEIVED
KANSAS CORPORATION COMMISSION

DEC 22 2006

CONSERVATION DIVISION
WICHITA, KS