

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-005-20172


COMPANY Halliburton Oil Producing

SEC. 8 T. 8 R. 21W
 LOC. SW NE NE

FARM Leck NO. 1

TOTAL DEPTH 3591'
 COMM. 10-2-68 COMP. 10-9-68
 SHOT OR TREATED
 CONTRACTOR Leben Drilling
 ISSUED 11-9-68

COUNTY Graham



CASING

20	10	
15	8 5/8" 321'	cem w/ 230 sx
12	6	
13	5	

ELEVATION 2020' KB

PRODUCTION DRY/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

0	60	Sand, Clay, Sand
60	100	Sand, Post Rock
100	590	Shale
590	1090	Sand, Shale
1090	1305	Sand
1305	1581	Shale, Red Bed
1581	1615	Anhydrite
1615	2495	Shale
2495	2675	Shale, Lime
2675	3185	Lime, Shale
3185	3590	Lime
	<u>3591</u>	<u>RTD - D. & A.</u>

8 5/8" 20# new surface casing set @ 321' cemented with 60/40 HA5

I Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Leck #1 Well, located SW NE NE of Section 8, Township 8 South, Range 21 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

TOPS: SMP	
Anhydrite	1582
Base Anhydrite	1616
Heebner	3190
Toronto	3218
Lansing	3232
Base Kansas City	3432
Arbuckle	3582
RTD	3590
LTD	3591