

32-8s-21W

15-065-21482

RECEIVED

STATE GEOLOGICAL SURVEY  
WICHITA BRANCHCONSERVATION DIVISION  
WICHITA, KANSAS

WICHITA, KANSAS

W E L L   L O G

S-2-5

OPERATOR: L &amp; A Oil Company

WELL NAME: P.N. Clark #2 LOCATION: S/2 NE SW 32-8s-21W

COUNTY: Graham STATE: Kansas

WELL COMMENCED: August 25, 1981 WELL COMPLETED: September 4, 1981

ELEVATION: 2192' K.B. TOTAL DEPTH: 3925'

PRODUCTION: Oil RIG NO: #2

CASING - 8 5/8": 8 Jts new 20# set @ 336.74' cemented with 185 sxs common 2%gel 3%cc  
P.D. @ 1:00 A.M. did circ. 8-26-81

5 1/2": 95 Jts new 14# set @ 3825' cemented 1st stage with 150 sxs common 10%salt

P.D. @ 3:45 P.M. cemented 2nd stage with 400 sxs 50-50 pos 6%gel P.D. @ 5:10 P.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING: 9-4-81 did cir

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	346'	sand and shale	346' - 1/4 degree	
346'	575'	shale		
575'	1140'	sand and shale		
1140'	1728'	sand and shale		
1729'	1754'	anhydrite		
1754'	1761'	anhydrite		
1761'	2000'	shale and sand		
2000'	2360'	lime and shale		
2360'	2585'	sand and shale		
2585'	2730'	lime and shale	2625' - 3 degree	
2730'	2915'	lime and shale		
2915'	3082'	shale and lime	3050' - 1 degree	
3082'	3212'	lime and shale		
3212'	3305'	lime and shale		
3305'	3400'	lime and shale		
3400'	3430'	lime and shale	3430' - 3/4 degree	
3430'	3445'	lime and shale		
3445'	3504'	lime and shale		
3504'	3566'	lime and shale		
3566'	3581'	lime and shale	3581' - 3/4 degree	
3581'	3600'	lime and shale		
3600'	3625'	lime and shale		
3625'	3713'	lime and shale		
3713'	3754'	lime and shale		
3754'	3788'	lime and shale		
3788'	3874'	arbuckle		
3874'	3925'	arbuckle		
3925'	R.T.D.			

STATE OF KANSAS