

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

505 East Murdock,

Wichita, Kansas

15-005-03089

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Glenn No. 1

SEC. 6 T. 8 R. 22W
C SE SE

Total Depth. 3655'

Comm. 1-8-59

Comp. 1-17-59


Shot or Treated.

Contractor. Imperial Oil of Kansas, Inc.

Issued. 4-4-59

County Graham

KANSAS



Elevation. 2192' RB

Production. 104 BOPD - NW

CASING:

8 5/8" 223' cem w/150 sx.
5 1/2" 3655' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay, sand & shale 223
shale & shells 485
shale & sand 1820
Anhydrite 1855
shale & shells 2330
shale & lime 3145
shale, shells & lime 3225
lime & shale 3310
lime 3655 RTD
Total Depth

TOPS:	SAMPLE	ELECTRIC LOG
Anhydrite	1820	
Heebner	3407	3406
Toronto	3428	3427
Lansing	3447	3446

DST #1 3438-61', op 1 hr., rec. 10' mud, BHP 50#.

DST #2 3505-16', op 2 hrs., rec. 600' gas, 240' very slightly mud cut oil, BHP 980#.

DST #3 3516-30', op 1 hr., rec. 3' very heavy oil, 35' mud, BHP 1070#.

DST #4 3562-88', op 1 hr., rec. 30' slightly oil cut mud, BHP 25#.

DST #5 3592-3610', op 1 hr., rec. 10' mud, BHP 0#.

DST #6 3608-27', op 1 hr., rec. 10' mud, BHP 0#.

DST #7 3622-55', op 1 hr., rec. 20' slightly oil cut mud, BHP 605#.