


**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

S. 6 T. 8 R. 22 **K**  
W

Loc. NE NW NW

County GRAHAM



Locate well correctly  
 Elev.: Gr. 2294

DF \_\_\_\_\_ KB 2303

API No. 15 — 065 — 21,196 ✓  
 County Number

Operator  
**Rains & Williamson Oil Co. Inc.**

Address  
**435 Page Ct., 220 W. Douglas, Wichita, KS 67202**

Well No. 1 Lease Name Jones "B"

Footage Location  
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Rains & Williamson Oil Co., Inc. Geologist Craig Caulk

Spud Date 4-12-80 Total Depth 3780' P.B.T.D.

Date Completed 4-21-80 Oil Purchaser

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	20#	214'	60/40 poz.	160 sx.	3% cc., 2% gel.

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbis.	Gas MCF	Water bbis.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. #1 Lease Name Jones "B"

S 6 T 8S R 22 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 3580-3609, 30 (30) 30 (45). Rec. 250' oil spotted mud. FP's 84-105, 105-107. IBHP 1156, FBHP 1156.			E. LOG TOPS	
			Anhydrite	1939 (+364)
			Heebner	3537 (-1234)
			Toronto	3562 (-1259)
			Lansing	3580 (-1277)
			BKC	3779 (-1476)
			LTD	3786 (-1483)
DST #2 - 3641-3648, 30 (30) 45 (30). Rec. 30' very heavy mud. FP's 21-21, 21-42. IBHP 1000, FBHP 989.				
DST #3 - 3668-3709, 30 (30) 30 (30). Rec. 15' mud w/oil spots. FP's 52-52, 52-52. IBHP 211, FBHP 211.				
DST #4 - 3704-3723, 30 (30) 30 (30). Rec. 5' OCM & 1' clean gassy oil. FP's 42-42, 42-42. IBHP 42, FBHP 42.				
DST #5 - 3719-3737, Miss-run.				
DST #6 - 3704-3737, 30 (30) 45 (30). Rec. 15' oil, 40' watery oily mud, 20' mud w/oil specks. FP's 105-105, 105-105. IBHP 127, FBHP 105.				
DST #7 - 3740-3758, 30 (30) 30 (30). Rec. 55' mud. FP's 52-52, 52-52. IBHP 317, FBHP 127.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains Signature

Wilson Rains

President

Title

5-12-80

Date

55070