

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-01930

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Glenn No. 2

SEC. 7 T. 8 R. 22W
C NW NE

Total Depth. 3647'
Comm. 1-18-59 Comp. 1-29-59
Shot or Treated.
Contractor. Imperial Oil of Kans.
Issued. 4-4-59

County Graham
KANSAS



CASING:

8 5/8" 218' cem w/150 sx.
5 1/2" 3647' cem w/125 sx.

Elevation. 2176' RB

Production. 307 BOPD - NW

Figures Indicate Bottom of Formations.

surface clay, sand & shale 218
shale & shells 860
shale & sand 1803
Anhydrite 1835
shale & shells 2100
lime & shale 3370
lime 3647
Total Depth

TOPS:	SAMPLE	ELECTRIC LOG
Anhydrite	1790	
Heebner	3382	3382
Toronto	3404	3406
Lansing	3420	3422
Base Kansas City	3624	3624

DST #1 3440-61', op 1/2 hr., rec. 870' salt water, BHP 1285#.

DST #2 3477-89', op 2 hrs., rec. 240' gas 90' muddy oil, 20' free oil, BHP 1045#.

DST #3 3491-3502', op 2 hrs., rec. 760' muddy salt water, 3' free oil, BHP 1050#.

DST #4 3541-65', op 1 hr., rec. 400' free oil, 100' muddy oil, BHP 1285#.

DST #5 3563'-80', op 1 hr., gas to surface in 50 mins., rec. 2200' clean gassy oil, BHP 865#.

DST #6 3580-98', op 2 hrs., rec. 355' gas, 125' oil cut mud, 60' froggy oil, BHP 1200#.

DST #7 3597-3614', op 2 hrs., rec. 60' gas, 80' oil cut mud, tool failed to close, no bottom hole pressure recorded.