

4-8-23W

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Petroleum, Inc.
Abercrombie Drilling, Inc.
JOHNSON 'A-B' #1
A/C SE NE SE Sec. 4-8S-23W
Graham County, Kansas
September 6, 1975
September 12, 1975


15.065.20,776

0	140	Surface dirt
140	210	Shale
210	381	Sand & Shale
381	1961	Shale & Sand
1961	1994	Anhydrite
1994	2645	Shale
2645	2920	Lime & Shale
2920	3240	Shale & Lime
3240	3670	Lime & Shale
3670	3810	Lime
	3810	Rotary Total Depth

Spudded in @ 10:15 a.m. September 6, 1975. Drilled 210' of 12 1/2" hole. Ran 5 jts. new 8 5/8" surface casing. Set @ 207.28'. Cemented with 150 sacks Sunset Cement. Cement circulated. Plug was down @ 2:00 p.m. September 6, 1975.

Plugged and Abandoned: 1st Plug Set @ 950' with 70 sx. cement; 2nd Plug Set @ 200' with 40 sx. cement; 3rd Plug Set @ 40' with 10 sx. cement. State Plugger: Gilbert Balthazor. Plug was down @ 2:00 p.m. September 12, 1975.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)




Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the JOHNSON 'A-B' #1, A/C SE NE SE Section 4-8S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of September, 1975.

Sandra Russell
Sandra Russell-Notary Public



Commission Expires: July 21, 1975