


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PEEL-HARDMAN OIL PRODUCERS
Farm- Legere No. 2

15-005-00295
SEC. 21 T. 8 R. 23W
CN¹/₂ SE NW SE
990' WL 1200' NL of SE/4

Total Depth. 3797
Comm. 9-6-52 Comp. 9-15-52
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 11-22-52

County Graham
KANSAS



CASING:

8 5/8" 210' cem.
5 1/2" 3791' cem.

Elevation. 2246

Production. Dry

Figures Indicate Bottom of Formations.

| | |
|-----------------|----------|
| surface soil | 210 |
| shale | 725 |
| sand & shale | 1890 |
| red bed & shale | 1945 |
| anhyd. | 1990 |
| shale & shells | 2340 |
| lime & shale | 2520 |
| lime | 2665 |
| lime & shale | 3415 |
| lime | 3795 RTD |
| lime | 3797 |
| Total Depth | |

| | |
|-------------|------|
| Tops: Scout | |
| Topeka | 3331 |
| Hoebner | 3543 |
| Lansing | 3583 |

Moved in cable tools 9-24-52 drilled
cem & deepened hole to 3797, az. w/500
gals. tested, ran Gamma Ray log & perf.
w/36 shots from 3786 to 3794, az. w/1500
gals., swabbed hole down; 9-27-52 tested
perf. w/ 36 shots from 3771-3778 az.
w/1000 gals., 9-28-52 bailed and tested,
set plug from 3767-3771, perf. w/24 shots from
3754-3762, test approx. 3 gals. oil per
hr.; 9-29-52 az. w/500 gals., swabbing, bailed
& tested, perf. from 3740-3746 w/18 shots
and from 3717-3730 w/37 shots az. w/2000
gals. bailed 2 1/2 bbls. oil & 8 gals. wtr.
per hr., tested further on 9-30-52,
no commercial show of oil, tore down
cable tools and moved out.