

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-005-02429

Company- DERBY OIL COMPANY
 Farm- McCoy "A" No. 1

SEC. 21 T. 8 R. 23W
 SW SW NE

Total Depth. 3745
 Comm. 1-7-52 Comp. 1-16-52
 Shot or Treated.
 Contractor. Glenn Peel Drlg. Co.
 Issued. 2-16-52

County Graham
 KANSAS



CASING:

Elevation. 2161 DF

8 5/8" 300' cem. w/175 sx, left in

Production. dry

Figures Indicate Bottom of Formations.

sand, 9" hole	90
shale	305
reamed to 12 1/4" hole	0-300
shale	750
sand & shale	1450
shale & Anhy.	2220
lime & shale	2600
lime	2740
lime & shale	3463
blk shale	3467
shale & lime	3504
chert, shale & lime	3540
lime & chert	3600
lime	3723
shale & lime	3745
Rotary Total depth	

Tops:	
Heebner	3463
Lansing	3504
Base Kansas City	3723

Drill Stem Tests

Lansing 3625 to 3640, 30", weak blow
 2", rec. 2' mud no BHP.
 Lansing 3645-3672, 30", weak blow
 3"; rec. 5' mud no BHP.
 Lansing 3680-3725, 30"; weak blow
 5", rec. 8' mud 500# BHP.

All measurements are from Kelly
 bushing