

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


15-005-19012

Company- IMPERAIL OIL of KANSAS, INC.  
Farm- Wilson "A" No. 1

SEC. 32 T. 8 R. 23W  
SE NW SW

Total Depth. 3902'  
Comm. 11-5-57 Comp. 12-6-57  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 3-1-58

County Graham  
KANSAS



CASING:  
8 5/8" 215' cem w/175 sx  
5 1/2" 3902'

Elevation. 2352' RB

Production. 30 BOPD / 70% wtr.

Figures indicate Bottom of Formations.

surface sand & clay	215
shale & sand	1335
shells & shale	1490
Dakota Sand	1740
shells & shale	2020
Anhydrite	2057
shale & shells	2365
shale & lime	3428
lime	3902-RTD
Total Depth	

<u>TOPS:</u>	<u>SAMPLE</u>	<u>ELECTRIC</u>
Anhydrite	2020	2019
Heebner	3646	3645
Toronto	3670	3670
Lansing	3687	3687

D.S.T. #1, 3710-20 open 2 hours. Rec.  
1520' Salt water. BHP 1250#.

D.S.T. #2, 3743-55 Open 2 hours. Rec.  
210' Salt water. BHP 830#.

D.S.T. #3, 3798-3825 Open 2 hours. Rec.  
700' gas, 80' heavily oil  
cut mud, 130' oil, 170' salt  
water. BHP 450#.

D.S.T. #4, 3824-44 Open 2 hours. Rec.  
390' gas, 90' heavily oil  
cut mud. BHP 1170#.

D.S.T. #5, 3844-65 Weak blow for 5 min.  
Packer failed.

D.S.T. #6, 3840-65 Open 2 hours, 430'  
gas, 110' heavily oil cut  
mud. BHP 1250#.

D.S.T. #7, 3861-3902 Open 1 hour. Rec.  
900' salt water. BHP 1100#.