

15-065-20899

State Geological Survey

WICHITA BRANCH  
KANSAS DRILLERS LOG

S. 36 T. 8S R. 23 ~~XX~~  
W

API No. 15 \_\_\_\_\_  
County \_\_\_\_\_ Number \_\_\_\_\_

Loc. NE SW SE

County Graham

Operator  
Murfin Drilling Company

Address  
617 Union Center, Wichita, Ks 67202


Well No. 2 Lease Name CASEY JONES "B"

Footage Location  
990 feet from ~~XX~~ (S) line 990 feet from ~~XX~~ (W) line SE/4

Principal Contractor Geologist  
Murfin Drilling Roger Welty

Spud Date Total Depth P.B.T.D.  
1/23/77 3830' 3803'

Date Completed Oil Purchaser  
3/18/77 Clear Creek



Locate well correctly  
Elev.: Gr. 2280'

DF. \_\_\_\_\_ KB. \_\_\_\_\_

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	119'	Common	100	
Production	7 7/8	4 1/2	9.5#	3829'	Class A + Latex A	125 50	10% salt + 3/4 CFB

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 golden jets		3717-20', 3734-37'
			+ 2 bullets/ft		3750-53'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8" EUE	3767.32'	--

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. Demud + a total of 2000 gal. of SS-20 acid	above intervals

INITIAL PRODUCTION

Date of first production 3/24/77		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 20.50 bbls.	Gas MCF	Water Tr.	Gas-oil ratio bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s) as above		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Murfin Drilling Company

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
Producer

Well No.

2

Lease Name

CASEY JONES "B"

S 36 T 8S R 23W E  
W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
surface clay		40	ANHYDRITE top	1907 +378
shale		212	base	1944 +341
shale and sand		1165	TOPEKA	3324 -1039
shale		1440	HEEBNER	3542 -1257
sand		1650	TORONTO	3563 -1278
shald and redbed		1907	LKC	3577 -1292
shale		3130	BKC	3799 -1514
shale and lime		3490	TD	3830
lime		3830		
RTD		3830		

DST #1: 3571-95/30-30-30-30, 45' M, 164-72-72-102, 111°.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Wm. S. Shropshire*  
Signature

Wm. S. Shropshire, Asst. Gen. Manager

Title

June 23, 1977

Date