



DRILL STEM TEST REPORT

Prepared For: **VJI Resources**

30-38 48th St
Astoria, NY 11103

ATTN: Jerry Green

31 8s 24w

Holley 6-C

Start Date: 2003.03.06 @ 14:18:25

End Date: 2003.03.06 @ 22:18:40

Job Ticket #: 16555 DST #: 1

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

VJI Resources

Holley 6-C

31 8s 24w

DST # 1

Lansing "1"

2003.03.06



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

VJI Resources
30-38 48th St
Astoria, NY 11103
ATTN: Jerry Green


Holley 6-C
31 8s 24w
Job Ticket: 16555 **DST#: 1**
Test Start: 2003.03.06 @ 14:18:25

GENERAL INFORMATION:

Formation: **Lansing "I"**
Deviated: No Whipstock: ft (KB)
Time Tool Opened: 16:30:10
Time Test Ended: 22:18:40
Interval: **3940.00 ft (KB) To 3960.00 ft (KB) (TVD)**
Total Depth: 3960.00 ft (KB) (TVD)
Hole Diameter: 7.79 inches Hole Condition:
Test Type: Conventional Bottom Hole
Tester: Wenrich
Unit No: 24
Reference Elevations: 2435.00 ft (KB)
2430.00 ft (CF)
KB to GR/CF: 5.00 ft

Serial #: 3310 **Inside**
Press@RunDepth: 54.21 psig @ 3941.00 ft (KB) Capacity: 7000.00 psig
Start Date: 2003.03.06 End Date: 2003.03.06 Last Calib.: 1899.12.30
Start Time: 14:18:30 End Time: 22:18:39 Time On Btm: 2003.03.06 @ 16:29:10
Time Off Btm: 2003.03.06 @ 19:30:55

TEST COMMENT: IF: Fair blow .1/2"-8 1/2" in bucket.
IS: No blow.
FF: Fair blow .1/4"-7 1/2" in bucket.
FS: No blow.



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2043.98	103.24	Initial Hydro-static
1	31.80	103.68	Open To Flow (1)
46	38.29	107.35	Shut-In (1)
91	1243.09	106.77	End Shut-In (1)
91	40.51	106.84	Open To Flow (2)
136	54.21	110.73	Shut-In (2)
182	1209.92	109.91	End Shut-In (2)
182	1880.80	109.96	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
90.00	gom 10%g 45%o 45%g	1.26

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

VJI Resources

30-38 48th St
Astoria, NY 11103

ATTN: Jerry Green

Holley 6-C

31 8s 24w

Job Ticket: 16555

DST#: 1

Test Start: 2003.03.06 @ 14:18:25

Tool Information

Drill Pipe:	Length: 3950.00 ft	Diameter: 3.80 inches	Volume: 55.41 bbl	Tool Weight: 2100.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 20000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: 90000.00 lb
			<u>Total Volume: 55.41 bbl</u>	Tool Chased 6.00 ft
Drill Pipe Above KB:	30.00 ft			String Weight: Initial 59000.00 lb
Depth to Top Packer:	3940.00 ft			Final 60000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	20.00 ft			
Tool Length:	40.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
C.O. Sub	1.00			3921.00	
S.I. Tool	5.00			3926.00	
HMV	5.00			3931.00	
Packer	4.00			3935.00	20.00 Bottom Of Top Packer
Packer	5.00			3940.00	
Stubb	1.00			3941.00	
Recorder	0.00	3310	Inside	3941.00	
Perforations	17.00			3958.00	
Recorder	0.00	10242	Outside	3958.00	
Bullnose	2.00			3960.00	20.00 Bottom Packers & Anchor
Total Tool Length:	40.00				



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

FLUID SUMMARY

VJI Resources

Holley 6-C

30-38 48th St
Astoria, NY 11103

31 8s 24w

Job Ticket: 16555

DST#: 1

ATTN: Jerry Green

Test Start: 2003.03.06 @ 14:18:25

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 46.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.19 in³

Gas Cushion Type:

Resistivity: 0.00 ohm.m

Gas Cushion Pressure:

psig

Salinity: 1000.00 ppm

Filter Cake: 0.20 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
90.00	gom 10%g 45%o 45%g	1.262

Total Length: 90.00 ft

Total Volume: 1.262 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

Serial #: 3310

Inside

VJI Resources

31 8s 24w

DST Test Number: 1

