

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-005-00446

Company- E. K. CAREY
Farm- Goff No. 1

SEC. 4 T. 8 R. 24W
NE SE SE

Total Depth. 3805'
Comm. 12-13-53 Comp. 12-30-53
Shot or Treated.
Contractor.
Issued. 3-6-54

County Graham
KANSAS



CASING:
8 5/8" 131' com w/85 sx
5 1/2" 3805' com w/100 sx

Elevation. 2327

Production. BHB 660 & tr. wtr.

Figures indicate Bottom of Formations.

base & cellar	8
clay	40
shale	130
shells	131
shale	1150
shale & shells	1600
sandy shale	1745
shale & shells	1750
red bed & shale	1995
lime & shale	2250
shale sandy	2415
shale & lime	2585
lime	2677
lime & shale	3050
lime	3095
lime & shale	3157
lime w/shale Brks.	3250
sandy lime	3260
lime & shale breaks	3324
lime w/shale Brks.	3406
shale & lime	3480
shale	3490
lime	3794
shale	3805 RTD
Total Depth	

Oil show 3738-45

Tops:
Heebner 3541
Lansing 3559
Base Kans. City 3794

DRILL STEM TESTS:

- #1 3728 to 3750. Open 1 hr. gas to top in 59 min. Recovered 2590' oil. 20 min BHP 1085#, IFP 200# and FFP 800#
- #2 3756 to 70. Open 20 min. quit blowing in 10 min. Recovered 10' rotary mud.

Set 5 1/2" on bottom w/100 sacks cement.
Centralizers @ 3775 and 3700.