


R.W.SHIELDS.
Paxson No. 1

SEC. 11 T. 8 R. 24W
NE NE

DISCOVERY WELL

Total Depth. 4100 equals 4104
Comm. 10-10-40 Comp. 11-5-40
Shot or Treated. 10-29-40?
Contractor. Harbar Drilling Co.
Issued. 3-8-41

County Graham.



CASING.

10" 105' 5 1/2" 3822'10"

Elevation.

Est. 200 to 300 B.

Production.

Pot. will be supplied later.

Figures Indicate Bottom of Formations.

shale and shells	130	shale	3684
limo shells	146	limo	3687
shale	375	shale	3695
limo	435	shale & limo	3715
shale	1006	limo soft	3719 sh oil
sand & S. shells	1080	limo and shale	3735
sand and shale	1280	limo	3778
shale	1425	shale	3794
sand	1440	limo	3815
shale	1540	limo and shale	3821
sand	1720	shale	3860
limo	1730	cherty limo	3890
shale & sand strks	1780	limo and shale	3910
shale & red bod	1870	shale	3920
red bod & shale	1945	limo	3940
anhydrito	1978	conglomerate	3965
shale	2165	limo (Arbucklo)	3979
shale & shells	2240	conglomerate & limo	4009
limo	2295	limo cherty	4019
shale & shells	2584	limo	4100
limo broken	2599	correction 4100 equals 4104	
shale & shells	2605	Total Depth.	
shale	2665		
shale & shells	2750		
limo & shale	2840		
shale	2895		
shale & limo (bkn)	2960		
broken limo	3010		
limo	3072		
shale & limo	3120		
broken limo	3184		
limo (Topoka)	3195		
limo	3435		
shale & limo	3475		
limo	3535		
shale blk	3539		
limo	3543		
shale	3552		
K.C. limo	3585		
limo	3596		
cherty limo	3614		
limo	3681		