

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02712

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Graham No. 2

SEC. 29 T. 8 R. 21W
NE SE NE

Total Depth. 3912'
Comm. 5-5-56 Comp. 5-15-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 8-11-56

County Graham
KANSAS



CASING:
8 5/8" 195' cem w/175 sx
5 1/2" 3900' cem.

Elevation. 2382' RB

Production. 360 B OPD, NW

Figures indicate Bottom of Formations.

sand and clay	50
shale	1055
sand and shale	1310
shale	1645
sand	1835
shale and red bed	2080
anhydrite	2115
shale and red bed	2345
shale	2460
lime and shale	2685
lime	2870
lime and shale	3550
lime	3912
Total Depth	

Tops:	
Anhydrite	2084
Heebner	3670
Toronto	3694
Lansing	3709

DST #1 3731-48', tool open 1 hr., rec. 180'
of oil cut mud, 240' of slightly water cut
oil. 30% water, also 120' of salt water.
IFP 50#, FFP 280#, BHP 1340#.

DST #2 3785-94', tool open 1 hr., rec. 2000'
of salt water. IF 385#, FF 1140#, BHP 1270#
in 20 mins.

DST #3 4794-3805', tool open 1 hr., rec. 2' of
mud. BHP 0# in 20 mins.

DST #4 3814-27, tool open 1/2 hr., rec. 25' of
mud with specks of oil. BHP 90# in 20 mins.

DST #5 3827-54', tool open 30 mins., rec. 6' of
mud, BHP 120# in 20 mins.

DST #6 3752-70', tool open 30 mins., rec. 10'
of mud. BHP 0# in 20 mins.

DST #7 3868-97, tool open 1 hr., rec. 600'
of gas, 330' of oil. IF 60#, FFP 155#, BHP
100# in 20 mins.