

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-005-30361

COMPANY TEXACO, INC.

SEC. 31 T. 8 R. 24W
 LOC. NW SW NE

FARM Holley Unit TR 7 NO. 4

TOTAL DEPTH 3985

COMM. 4-16-66


COMP. 5-19-66

SHOT OR TREATED

CONTRACTOR Leben Drlg.

ISSUED 6-18-66

COUNTY Graham
 KANSAS



CASING

20	10	
15	8 5/8"	@ 313' w/215 SX.
12	6	
13	5 1/2"	@ 3984' w/100 SX.

ELEVATION 2428' KB

PRODUCTION Injection

FIGURES INDICATE BOTTOM OF FORMATIONS

0	40	Clay, Sand, Post Rock	
40	90	Sand	
90	940	Shale	
940	1125	Sand, Shale	
1125	1590	Shale, Sand	
1590	2133	Redbed	TOPS: SAMPLE
2133	2168	Anhydrite	
2168	2253	Shale	Toronto 3741
2253	2659	Shale, Shells	Lansing 3757
2659	2910	Shale, Lime	
2919	3750	Lime, Shale	
3750	3910	Lime	
3910	3944	Core	
3944	3985	Lime	
	3985	RTD - Set 5 1/2" Casing	

Set 8 5/8" 8 rd. 20.2# used surface casing @ 313' with 215 sacks
 Posmix, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Holley Unit Tr. 7-#4, located NW SW NE Section 31, Township 8 South, Range 24 West, of Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 26th day of April, 1966.