

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-02751

Company. HERMAN GEORGE KAISER
Farm-Keith No. 4

SEC. 32 T. 8 R. 24W
C E/2 NW
660' W & 1320' N-SE NW

Total Depth. 3930
Comm. 12-10-55 Comp. 12-18-55
Shot or Treated.
Contractor. K & E Drilling, Inc.
Issued. 4-21-56

County Graham
KANSAS



8 5/8 @ CASING: 211' w/ 150 sx cmt.
5 1/2 @ 3930' w/ 150 sx cmt.

Elevation. 2364 RB

Production. 153 BOPD

Figures indicate Bottom of Formations

cellar	8
soil & clay	70
shale	211
shale & shells	350
shale	925
shale & shells	1555
sand	1820
red bed & shale	2061
anhydrite	2100
shale & shells	2605
shale & lime	3697
lime	3930
Total Depth	

TOPS:	
Heebner	3666
Toronto	3691
Lansing	3709
Base K. C.	3918

No electric log run.

DST #1: 3853-70, open 1 hr. rec. 360'
gas; 20' SOCM, 115' HOCCM, 5' clean
oil, BHP 860#/15 min.