

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-005-02755

Company- IMPERIAL OIL OF KANSAS, INC.  
Farm- Keith "A" No. 2

SEC. 32 T. 8 R. 24W  
CS/2 SE SE

Total Depth. 3962'  
Comm. 1-18-56 Comp. 1-28-56  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 4-7-56

County Graham  
KANSAS



Elevation. 2443' RB

Production. 402 BOPD

CASING:

8 5/8" 224' cem w/175 sx  
5 1/2" 3962' cem.

Figures indicate Bottom of Formations.

shale, sand & shells	1540
shale & shells	1165
Dakota sand	1895
shale & shells	2145
anhydrite	2185
shale & shells	2800
lime & shale	3615
lime	3652
lime & shale	3725
lime	3962
Total Depth	

Tops:

Anhydrite	2145
Heebner	3736
Toronto	3760
Lansing	3775

DRILL STEM TESTS:

#1 3914-37', open 2 hrs., rec. 420' gas,  
100' oil cut mud, 5' mud cut oil. FP 6#-45#,  
BHP 540#.

#2 3940-62', open 1/2 hr., rec. 300' gas, 50'  
heavy oil cut mud, 60' free oil. FP 35#-100#  
BHP 1265#.