


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Keith "A" No. 5

SEC. 32 T. 8 R. 24W
 C S/2 SW NE

Total Depth. 3940'
 Comm. 11-4-56 Comp. 11-20-56
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 1-12-57

County Graham, KANSAS



Elevation. 3290' RB

Production. 95 BOPD, no water

CASING:

8 5/8" @193' w/150 sx cem.
 4 1/2" @3940' cemented

Figures indicate Bottom of Formations.

surface sand & rock	25
sand & yellow clay	90
shale & shells	930
sand & shale	1530
sand	1575
shale, red bed & sand	1665
sand	1850
shale & red bed	2085
Anhydrite	2125
shale & shells	2485
shale & lime	3690
lime	3940 RTD
Total Depth	

TOPS

Anhydrite	2090
Heebner	3686
Toronto	3713
Lansing	3728

DRILL STEM TESTS

DST #1, 3870-93, Op. 2 hrs.
 Rec. 70' heavy OCM, B.H.P. 130#.

DST #2, 3908-40, op. 1/2 hr.
 Rec 10' mud, B.H.P. 100#.