

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02760

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Keith "B" No. 4

SEC. 32 T. 8 R. 24W
SE SW SW

Total Depth. 3985
Comm. 5-18-57 Comp. 6-3-57
Shot or Treated.
Contractor. Harms-Burt Drilling Co.
Issued. 7-20-57

County Graham
KANSAS



CASING:
8 5/8 @ 215' w/ 175 sx cmt.
5 1/2 @ 3985' w/ 125 sx cmt.

Elevation. 2447 RB

Production. 3000 BOPD, NW

Figures indicate Bottom of Formations.

sand & clay	110
shale & shells	1050
sand & shale	1470
shale & shells	1710
sand	1900
shale & red bed	2050
anhydrite	2185
shale & shells	2800
lime & shale	3730
lime	3985
Total Depth	

TOPS:
Anhydrite 2134
Heebner 3723
Toronto 3748
Lansing 3764

DST #1: 3784-3801, open 1 hr. rec.
1000' gas, 2000' oil, BHP 1200#

DST #2: 3801-26, open 2 hrs. rec.
50' HOCM, BHP 760#.

DST #3: 3841-48, open 2 hrs. rec. 70'
HOCM, 10' muddy wtr. FP 35-50#, BHP
1250#

DST #4: 3880-3905, open 1 hr. rec.
2400' gas, 440' oil, BHP 810#.