

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02701

Company. IMPERIAL OIL OF KANSAS, INC.
Farm. Brown "D" No. 2

SEC. 33 T. 8 R. 24W
S/2 SE SW

Total Depth. 4010
Comm. 8-19-55 Comp. 8-29-55
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 10-29-55

County Graham
KANSAS



CASING:
8 5/8 @ 220' w/ 175 sx cmt.
5 1/2 @ 4010' cmtd.

Elevation. 2450 RB

Production. 397 BOPD, no wtr.

Figures indicate Bottom of Formations.

sand & shale	220
shale & shells	1170
sand & shale	1655
Dakota sand	1900
shale & shells	2144
anhydrite	2180
shale & shells	2690
shale & lime	3701
lime	4010
Total Depth	

TOPS:	
Anhydrite	2144
Heebner	3740
Toronto	3766
Lansing	3782

DST #1: 3802-20, open 2 hrs. rec.
900' wtr. IFP 60#, FFP 450#, BHP
1065#/20 min.

DST #2: 3822-38, open 1 hr. rec. 80'
free oil, 20' raw load acid, IFP 60#,
FFP 60#, BHP 1125#/20 min.

DST #3: 3929-41, open 2 hrs. rec.
2000' gas, 320' free oil, IFP 60#,
FFP 150#, BHP 1035#/20 min.

DST #4: 3949-70, open 2 hrs. rec. 20'
CCM, 60' raw load acid, IFP 60#,
FFP 60#, BHP 90#/20 min.