


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company-IMPERIAL OIL OF KANSAS, INC.
Farm-Davis No. 1

SEC. 5 T. 8 R. 25W
SE SW SW

Total Depth. 4015
Comm. 6-20-57 Comp. 6-29-57
Shot or Treated.
Contractor. Harms-Burt Drilling Co.
Issued. 8-3-57

County Graham
KANSAS



CASING:

8 5/8 @ 218' w/ 175 sx cmt.

Elevation. 2511 RB

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	140
shale & shells	625
sandy shale	675
shale	985
sand	1240
shale	1470
shale, shells & sand	1975
red bed & shale	2200
anhydrite	2230
shale & shells	2650
shale & lime	3085
lime	3315
lime & shale	3720
lime	4015
Total Depth	

TOPS:	
Anhydrite	2200
Heebner	3756
Toronto	3777
Lansing-KC	3794
Base KC	4004

DST #1: 3814-35, open 1 hr. rec. 40'
muddy SW, BHP 1080#

DST #2: 3910-30; open 1 hr. rec. 180'
gas, 55' SO&GCM, BHP 1170#

DST #3: 3943-60, open 1 hr. rec. 15'
mud, BHP 150#