

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-00646

Company. HARMS-BURT DRLG.
Farm- Schmied No.1

SEC. 20 T. 8 R. 25W
SE SE SE

Total Depth. 3925'
Comm. 7-22-60 Comp. 7-31-60
Shot or Treated.
Contractor.
Issued. 3-11-61

County Graham
KANSAS



CASING:

8 5/8" 205' cem w/1750 sx.

Elevation. 2393' KB

Production. Dry

Figures Indicate Bottom of Formations.

sand	60
shale & sand	170
shale	400
shale & sand	620
shale blue & gray	1050
shale & sand streaks	1500
shale	1630
red bed & sand	1925
red bed, shale & shells	2106
anhydrite	2145
shale & shells	2540
shale	2750
lime & shale	3715
lime	3917
shale	3925
Total Depth	

TOPS:

Anhydrite	2106
Heebner	3652
Toronto	3676
Lansing	3692
Base Kansas City	3909

DST #1 3710-3730', op 1 hr, shut in 20
mins, rec. 25' slightly gas cut mud
w/few spots of oil. IBHP 1215#, FBHP 1070#.

DST #2 3806-3830', op 30 mins, shut in 20
min, rec. 5' mud. IBHP 820#, FBHP 560#.

DST #3 3844-3870', op 45 mins, shut in
20 min, rec. 5' mud, IBHP 70#, FBHP 25#.

Ran Electric Log.