

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


15-065-02791

Company- C. U. BAY
 Farm-Schmeid "B" No. 1

SEC. 20 T. 8 R.25W
 NE NE NE

Total Depth. 3889
 Comm. 7-6-54- Comp.8-26-54
 Shot or Treated.
 Contractor, Empire Drilling Co.
 Issued. 10-2-54

County Graham
 KANSAS



Elevation. 2369 DF

Production. I Pot. 494 BO,
 no water

CASING:

8 5/8 202' w/ 125 sx cmt.
 5 1/2 3884' w/ 125 sx cmt.

Figures Indicate Bottom of Formations.

sand & shale	218
shale	525
shale & sand	1375
shale & shells	1830
shale	2073
anhydrite	2110
shale	2175
shale & shells	2605
shale	2720
shale & lime	2890
shale & shells	3015
lime	3170
shale & lime	3270
lime	3440
lime & shale	3705
lime	3889
Total Depth	

TOPS:

Heebner	3622
Toronto	3646
Lansing	3660

DST #1: 3722-54, open 1 hr. rec. 30'
 mud, BHP 0#

DST #2: 3775-97, open 1 hr. rec. 5'
 mud, BHP 110#

DST #3: 3804-37, open 1 hr., gas in
 45', rec. 1300' free oil, BHP 480#/
 20 min. FP 420#

Perf. 32 & 3828-36
 Swab 16 BOPH nat. 3000 acid
 Pump 140 BO/12 hrs.