


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. TENNESSEE GAS TRANSMISSION CO.
Farm. Schmied "B" No. 2

SEC. 20 T. 8 R. 25W
C N/2 N/2 NE

Total Depth. 3937
Comm. 11-27-55 Comp. 1-4-56
Shot or Treated. Perf. 47/3852-50: 1000 gal acid.
Contractor. Sterling Drilling Co.
Issued. 2-11-56

County Graham
KANSAS



8 5/8 @ CASING: 229' w/ 175 sx cmt.
5 1/2 @ 3898' w/ 100 sx cmt.

Elevation. 2387 RB

Production. 51.77 BOPD, NW

Figures indicate Bottom of Formations

clay & shale	238
shale	2500
shale & lime	2705
shale	2905
shale & lime	3680
lime	3865
lime & shale	3937
Total Depth	

TOPS:
Heebner 3643
Lansing 3685

DST #1: 3695-3725; open 1 hr, SI 20
min. rec. 45' mud, 20' wtr. wk. bl.
BHP 1185#

DST #2: 3755-70, open 1 hr SI 20 min.
rec. 25' mud, BHP 0#

DST #3: 3796-3830, open 1 hr. SI 20
min. rec. 5' mud, BHP 110#

DST #4: 3828-65, open 1 hr. SI 20 min.
wk. bl. 4 min. rec 15' rtry mud. w/
few specks oil, BHP 60#