

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00281

Company- C. U. BAY PETROLEUM
 Farm- Schmied "A" No. 1

SEC. 21 T. 8 R. 25W
 NW NW SE

Total Depth. 4474
 Comm. 3-19-52 Comp. 5-6-52
 Shot or Treated.
 Contractor. Anschutz Drilling Co.
 Issued. 7-12-52

County Graham
 KANSAS



CASING:

8 5/8" 265 cem. w/150 sx.
 5 1/2" 3950

Elevation. 2384

Production. 68.18 bbls. /
 5% wtr.

Figures Indicate Bottom of Formations.

surface clay	180
shale	985
sand & shale	1335
shale & shells	1600
shale	1665
red rock	2080
red rock & shale	2135
anhyd.	2180
shale	2225
shale & shells	2830
lime & shale	3728
lime	3926
lime & shale	4237
cherty lime	4258
Miss. chat	4273 1/2
Miss. lime	4290
lime	4354
dolo.	4470 RTD
dolo.	4474
Total Depth	

Tops:	
Topeka	3452
Heebner	3675
Lansing	3717
Congl.	4233
Miss. chert	4249
Miss. lime	4285
Viola	4326
Arbuckle	4400

D.S.T. 3733-51 open 1 hr. Rec. 215' oil /
 220' muddy oil in 15" BHP 900 # F.P. 120#.
 D.S.T. 3781-98 open 1 hr. Rec. 2035 SOCW
 BHP 1330# F.P. 895#.
 D.S.T. 3829-43 open 1 hr. Rec. 15'
 oil & HOCM 1150# BHP D.S.T. 3874-93
 open 1 hr. Rec. 450' gas 30' free oil.
 60' SMC oil. 1300# BHP 720# F.P.
 Perf. 12 / 3878-81 - 34 to 36 GPH/9 hr.
 1000 acid max 425#. 12 BO/4 hrs. Plug 3870
 Perf. 3838-44 swab 10 to 12 BPH/2 hrs.
 Plug lose @ 3870. Set another plug @ 3810.
 24 / 3740-44 200' OIH / SW. 500 acid
 Swab 47 BO/4 hrs.
 3-6-52 68.18 BO / 5% wtr. State Test.