

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02257

Company- BAY PETROLEUM CORPORATION
Farm- Schmied "C" No. 4

SEC. 21 T. 8 R. 25W
C NW/4

Total Depth. 3910
Comm. 10-10-54 Comp. 10-19-54
Shot or Treated.
Contractor. i. . . Jackson Drilling Co.
Issued. 11-6-54

County Graham
KANSAS



Elevation. 2387

CASING:
8 5/8 190'

Production. Dry

Figures indicate Bottom of Formations.

surface soil, shale & sand	218
shale	1015
shale & shells	1370
lime & shale	1420
shale & shells	1640
red bed	1650
shale	1860
shale & shells	2100
anhydrite	2135
shale & shells	2820
lime	2885
shale & shells	2980
shale & lime	3010
lime & shale streaks	3050
lime & shale breaks	3150
lime	3207
shale & lime streaks	3455
lime & shale	3680
lime	3715
shale & lime	3770
lime	3825
lime & shale	3880
lime	3910
Total Depth	

TOPS:

Heebner	3633
Toronto	3656
Lansing	3673

DST #1: 3691-3712, open 1 hr. SI 20 min, rec. 700' muddy SW,

DST #2: 3721-38, open 1 hr. SI 20 min. rec. 20' drlg. mud, BHP C#

DST #3: 3810-77, open 1 hr. SI 20 min. rec. 28' drlg. mud. BHP C#

3907' DF Total Depth