

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

30-8-25W

COMPANY DANE G. HANSEN ESTATE

SEC. 30 T. 8 N. 25W

FARM Hansen Estate Fee NO. 2

LOC. C NE SE

15-065-20001

TOTAL DEPTH 4030

COMM. 1-9-67

COMP. 1-20-67


SHOT OR TREATED

CONTRACTOR C-G Drllg.

ISSUED 4-15-67

COUNTY Graham

KANSAS



CASING

20	10	
15	8	5/8" @ 205.46' w/150 SX
12	6	
13	4 1/2"	@ 4039.14' w/125 SX

ELEVATION 2517' KB

PRODUCTION PMP 124 BOPD/NW
 LANS 3912-54

FIGURES INDICATE BOTTOM OF FORMATIONS

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1825	SHALE	500' 1/4°	
1825	1985	SAND	1000' 1/4°	
1985	2080	SHALE & RED BED	1500' 3/4°	
2080	2215	SHALE	2280' 1°	
2215	2254	ANHYDRITE	2625' 3/4°	
2254	2600	SHALE & SHELLS	3100' 1/2°	
2600	2730	LIME & SHALE	3824' 3/4°	DST #1 3779-3796
2730	2865	LIME		DST #2 3803-3824
2865	3075	SHALE & LIME		DST #3 3842-3870
3075	3160	LIME & SHALE		DST #4 3891-3926
3160	3260	LIME		DST #5 3926-3946
3260	3450	LIME & SHALE		DST #6 3926-3966
3450	3550	LIME		DST #7 3969-4030
3550	3690	LIME & SHALE		
3690	4030	LIME		

TOPS: SCOUT

Anhydrite	2215
Howard	3429
Heebner	3749
Toronto	3773
Lansing	3785
Base Kansas City	4015

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C. C. DRILLING CO.