

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

15-065-02781

Company- CHAMPLIN REFINING CO.
Farm- Paxson No. 1

SEC. 16 T. 8 R. 25W
NE NE NE

Total Depth. 3965'

Comm. 11-28-54


Comp. 12-10-54

Shot or Treated.

Contractor.

Issued. 1-22-54

County Graham
KANSAS



CASING:

8 5/8" 212.71' cem w/150 sx
5 1/2" 3961' cem w/150 sx

Elevation. 2408' BB

Production. 14 BO

Figures indicate Bottom of Formations.

surface dirt	30
sand and gravel	70
clay - shale	216
clay - shale	560
clay and shale	1000
shale and sand	1060
clay and shale	1230
shale and shells	1400
shale and lime shells	1560
sandy shale	1710
red shale	1950
green and red shale	2040
red shale	2120
anhydrite	2149
shale and shells	2300
gray and green shale	2390
broken lime & gray shale	2530
shale and shells	2680
shale and lime	2730
shale and lime breaks	2880
shale and lime shells	3060
lime and shale	3080
shale and lime shells	3185
shale and lime	3440
lime	3463
shale and lime	3510
lime	3645
shale and lime	3705
lime	3874
shale	3881
lime	3936
shale	3940
sand	3965
Total Depth	

Tops:

Heebner	3679
Toronto	3704
Lansing	3718
Base Kansas City	3935

DRILL STEM TESTS:

- #1 3860-78, op. 1 hr. weak blow thruout
Rec. 90' gas in drill pipe & 30' gassy
OCM FP 0# 20" BHP 975#
- #2 3881-93, op. 45" Weak blow 8" Rec. 1'
mud w/ very slight show oil FP 0#
15" BHP 50#
- #3 3917-36, op. 45" Rec. 3' drlg. mud.
FP 0# 15" BHP 50#