

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-179-00178

Company- EMPIRE DRILLING COMPANY
Farm- Davis No. 1

SEC. 1 T. 8 R. 26W
NE NE NE

Total Depth. 3900
Comm. 8-29-56 Comp. 9-6-56
Shot or Treated.
Contractor. Empire Drlg Co.
Issued. 9-29-56

County Sheridan
KANSAS



CASING:
8 5/8" 179' cem w/115 sx

Elevation. 2455 K.B.

Production. Dry

Figures indicate Bottom of Formations.

shale, sand	197
shale, shells	600
shale, sand	1306
shale, shells	2140
anhydrite	2159
shale, shells	2645
shale, lime	3232
shale, shells	3375
shale, lime	3495
shale, shells	3661
lime	3900
Total Depth	

Tops:
Anhydrite (Scout) 2140
Heebner 3637
Toronto 3659
Lansing K. C. 3675

DST #1 3690-3715 Tool open 1 hr.
Weak blow for 16 min., Rec.
35' of mud w/few spots of
oil. 30 min. shut-in BHP
1240#.

DST #2 3792-3815 Tool open 1 hr.
Weak blow for 6 min. Rec.
5' of mud. 20 min. shut-in
BHP 0#.