

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-8-26W

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Twell No. 1

SEC. 15 SE NW T. 8 R. 26W
15-179-00113

Total Depth. 4450
Comm. 6-11-55 Comp. 6-24-55
Shot or Treated.
Contractor. IMPERIAL OIL OF KANSAS, INC.
Issued. 7-30-55

County Sheridan
KANSAS



CASING:
8 5/8 @ 228' w/ 175 sx cmt.

Elevation. 2447 RE.

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	228
shale, shells & sand	525
shale & shells	1350
sand & shale	1685
Dakota sand	1840
sand, shells & red bed	2080
anhydrite	2117
shale & shells	2355
shale & lime	3610
lime	4450
Total Depth	

Anhydrite	2080
Heebner	3604
Toronto	3625
Lansing	3645
Base KC	3860
Marmaton chert	3992
Mississippi chert	4183
Mississippi lime	4222
Gilmore City lime	4263
Viola	4302
Arbuckle	4399

DST #1: 3762-80, open 1 hr., rec. 20'
mud, BHP 1180#/20 min.

DST #2: 3791-3813, open 1 hr., rec. 6'
mud, BHP 0#/20 min.

DST #3: 3819-34, open 1 hr., rec. 6'
mud, BHP 0#/20 min.

DST #4: 4187-4216, open 1/2 hr., rec.
40' mud, IFP 0#, FFP 30#, BHP 1120#/
20 min.